

2513

1998 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 34 N R 4 E	G-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

PRESQUE ISLE COUNTY  
RECORDED

98 DEC 17 PM 4:26

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Delmer E. Porter in a field survey on Jan. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-9 GLO NOTES  
June 27, 1856  
Set Post Cor of Sec 21, 22, 27 & 28  
Beech 12 S44E 48 Links  
Sugar 12 N30W 36 Links

SURVEY &  
REMONUMENTATION

JAN 14 1999


SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Spike  
S42°W 65.82' 8" Maple  
S22°W 79.75' 12" Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 1/2" Rod  
N63°E 56.38' Anchor Pole  
S25°W 79.80' 18" Maple  
S44°W 66.49' 10" Maple  
N67°W 71.72' FE Post 6"X6" RR Tie



Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *William J. Quinn*  
Date 12/17/98

Signed by *Delmer E. Porter*  
Surveyor's Michigan License No. #15410

Date Jan 9, 1998