

3517

1998 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>34</u> N R <u>4E</u>	<u>G-13</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

PRESQUE ISLE COUNTY  
RECORDED

98 DEC 17 PM 4: 26

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Delmer E. Porter in a field survey on Jan. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 GLO Notes - June 20, 1856	Town Cor 4X4 (Very Old)
Set Post cor Sec 33 & 34	N70°W 19.65' 7" Cedar
Cedar 6 N57W 15'	N25°E 23.48' 9" Cedar
Do 12 N57E 7'	S55°W 10.40' 16" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Conc. Mon/Brass Cap  
S40°W 19.21' 7" Cedar

Ratified by Peer Group  
in accordance with P.A. 345

Chairman *William J. Quinn*

Date 12/17/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Conc. Mon w/Brass Cap  
N54°W 19.86' 8" Cedar  
N79°W 8.82' 12" W. Pine  
S67°W 10.37' 16" Cedar  
S38°W 10.37' 16" W. Pine  
Single Wire FE running N-E-S-W



SURVEY &  
REMONUMENTATION

JAN 14 1999

SECTION

Signed by *Delmer E. Porter*  
Surveyor's Michigan License No. #15410

Date Dec 9, 1998