

520

LIBER 329 PAGE 888

1998 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T4N R4E	H-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY  
RECORDED  
98 DEC 17 PM 4:27  
*Janet M. Lamb*  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Delmer E. Porter in a field survey on July 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5								●					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-5 GLO Notes  
June 26, 1856  
Set Quarter Section Post  
Beech 5 S58W 27 Links  
Y Birch 6 N52E 32 Links


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 1/2" Rod & Cap #33984  
N01°E 3.93' 6" Maple  
N89°E 15.52' 6" Maple  
S16°E 19.53' 5" Birch  
S21°W 12.97' 4" Balsam

SURVEY &  
REMONUMENTATION  
JAN 14 1999  
SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 1/2" Rod & Cap #33984  
N01°E 3.93' 6" Maple  
N89°E 15.52' 6" Maple  
S16°E 19.53' 5" Birch  
S21°W 12.97' 4" Balsam



Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Norman J. Quinn*  
Date 12/17/98

Signed by Delmer E. Porter  
Surveyor's Michigan License No. #15410

Date Dec 9, 1998