

356

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle County (County)	Located in: Bismarck	Corner Code #
1. Public Land Survey	T 34N R 4E	I-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

98 NOV 25 AM 11:13

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James A. Beck, in a field survey on August 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-3
1856 G.L.O. by Alfred Millerd
"Set post cor. Secs. 2,3,10 & 11"
Beech 14 N48W 31
Hemlock 14 S55E 11

SEE REVERSE SIDE OF SHEET
FOR CONTINUATION PART "A"

SURVEY &
REMONUMENTATION

JAN 14 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found concrete monument / Brass cap
Note: December 1, 1995 Recordation appears in error all witnesses and said 1/2" iron rod were not found.
Monument found at this corner conforms with 1978 recordation by Delmer E. Porter
Witnesses found: S 74°W 73.46', 6" White Pine, P.S. 15410 tag (old recorded witness); N 85°E 67.63', 14" Red Pine, P.S. 15410 tag (apparent old witness); S 65°W 51.84', 10" Oak, P.S. 15410 tag (apparent old witness)

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Norman J. Osmani*
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 concrete monument / Brass cap
Witnesses:
S 74°W 73.46', 6" White Pine, P.S. 15410 tag
N 85°E 67.63', 14" Red Pine, P.S. 15410 tag
S 65°W 51.84', 10" Oak, P.S. 15410 tag
set 2 additional witnesses:
N 59°E 38.12', 8" Oak, P.S. 21559 tag
S 51°E 78.61', 12" Red Pine, P.S. 21559 tag



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan
Remonumentation**

Bismarck Township, T34N, R4E

Corner code: I-3 CORNER COMMON TO SECTIONS 2, 3, 10, & 11

Date: Activity, Monument & Accessories:

**Date not noted: from Volume on file in Register of Deeds office, labeled
" Established Section Corners"
Entry believed to have been made by G.F. DeLaMater
W. Birch 7 S34W 62.5, (spike)
Hem 6 N77W 204.8
½"x 24" bar in cor.**

**November 9, 1978 P.A. 74 (Land Corner Recordation) Certificate by Delmer E. Porter No.
15410
Part A. (of certificate)
" ½" bar (G. DeLaMater)
N 77°W 204.8' 6" Hemlock
S 34°W 62.5' 7" Birch
Part B. "same as above"
Part C. Conc. Mon./Brass Cap
N 75°E 70.63' 6" Pine
S 59°E 73.02' 5" Pine
S 74°W 73.65' 4" Pine**

**December 1, 1995 P.A. 132 Certificate by Norman J. Quaine No. 33984
SE Cor.
Sec. 3, T34N, R4E
½" rod & Cap #15410
N 19°E 21.64' 4" Spruce
N 35°W 39.05' 4" Maple
N 48°E 6.70' 4" Maple
N 63°E 11.30' 5" Maple**