

2359

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle County (County)	Located In: Bismarck	Corner Code #
1. Public Land Survey	T 34N R 4E	I-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

98 NOV 25 AM 11:14

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on August 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-6 1856 G.L.O. by Alfred Millerd
"Set 1/4 Sec. post"
W. Birch 10 N60W 16
W. Pine 6 S40E 25

SEE REVERSE SIDE OF FORM FOR CONTINUATION
OF SECTION "A."

SURVEY &
REMONUMENTATION

JAN 14 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found 1 1/2" pipe with 1/2" re-rod and 15410 cap inside of pipe
guarded by a carsonite post.
All witnesses from February 1997 recordation
are in good condition, witnesses marked by spikes.

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Norman J. [Signature]*
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 1 1/2" pipe with 1/2" re-rod and 15410 cap inside of pipe
guarded by a carsonite post
Witnesses marked by spikes.
7" Maple in cluster of 3 N34°W 30.17'
6" Maple S 81°W 41.14'
6" Maple in cluster of 3, S53°E 44.59'
SW Cabin corner N64°E 87.48'



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan
Remonumentation**

Bismarck Township, T34N, R4E

Corner code: I-6 1/4 Corner common to Sections 14 and 15

PART "A" CONTINUED

**March 20, 1981 P.A. 74 (Land Corner Recordation Certificate) by Delmer E. Porter
No. 15410**

Part A: (of Certificate)

"I-6 (nothing)"

**Part B: "Found 1 1/2" Pipe 3' out of line between Sec. Cors. and
10' North of Single Proportion.
accepted."**

Part C: 1 1/2" Pipe/1/2" Rod & Cap inside

N34°W 30.18 5" Maple

S 81°E 41.17' 5" Maple

S 53°E 44.64' 6" Maple

**February 27, 1997 P.A. 74 (Land Corner Recordation Certificate) by Carl T. Kiiskila
No. 33981**

Part A: (of certificate)

no entry

**Part B: "Found and accepted a 1 1/2" pipe as witnessed by Delmar
Porter, RLS, found on page 563 of Presque Isle Co.
L.C.R.C's . The corner fits G.L.O. swamp ties South well.**

Part C: Found 1 1/2" pipe with 1/2" rebar & D. Porter RLS CAP

7" Maple N34°W 30.17'

6" Maple S 81°W 41.14'

6" Maple S53°E 44.59'

SW Cabin corner N64°E 87.48'