

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Presque Isle County  
(County)

Located in: Bismarck

Corner Code #

1. Public Land Survey T 34N R 4E I-7  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R

3. Miscellaneous Property in Sec. S T R  
S T R

PRESQUE ISLE COUNTY  
RECORDED

98 NOV 25 AM 11:14

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James A. Beck, in a field survey on August 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1-7 1856 G.L.O by Alfred Millard  
"Set post Cor. Secs 14, 15, 22 & 23"  
W. Birch 10 S62W 30  
Maple 9 N30E 13

SEE REVERSE SIDE OF FORM FOR CONTINUATION  
OF SECTION "A."

SURVEY & REMONUMENTATION

JAN 14 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1-7 Found corner as monumented and recorded in Feb. 27, 1997  
recording.  
All witnesses as recorded Feb 27, 1997 are marked  
by P.S. 15410 tags  
Set 1 new witness:  
N 10°E 15.20', P.S. 21559 tag in 8" Maple

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *William J. ...*  
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1-7 1" x 32" iron pipe w/alumn.  
DNR cap guarded by a carsonite Post.  
4" W. Pine N78°E 23.68' (PS 15410 tag)  
12" Maple N62°W 35.32' " " "  
18" Oak S18°W 16.89' " " "  
6" Maple S29°E 27.19' " " "  
N 10°E 15.20', P.S. 21559 tag in 8" Maple



Signed by *James A. Beck*  
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan  
Remonumentation**

Bismarck Township, T34N, R4E

Corner code: I-7 Corner common to Sections 14, 15, 22, & 23

Part "A" CONTINUED:

December 18, 1996 P.A. 74 (Land Corner Recordation Certificate) by Thomas G. Hall

No. 41100

Part A: (of certificate)

½" Rod

N60°W 35.22' 6" Maple

N75°E 23.63' 3" W. Pine

S30°W 16.75' 14" Oak

Part B: fd. ½" Rod- Put cap #33984 on

at Fence Corner

N62°W 35.33' 10" Maple

N70°E 23.63' 4" W. Pine

S18°W 16.87' 18" Oak

Part C: ½" Rod & Cap #33984

at Fence Corner

N62°W 35.33' 10" Maple

N70°E 23.63' 4" W. Pine

S 29°E 27.20' 6" Maple

S18°W 16.87' 18" Oak

February 27, 1997 P.A. 74 (Land Corner Recordation Certificate) by Carl T. Kiiskila

No. 33981

Part A: (of certificate)

"(No evidence of G.L.O. corner, B.T's, line trees & topography, as called out in the G.L.O. line notes; unless noted in item "B"below.)"

Part B: "Found and accepted a ½" rebar with D. Porter RLS Cap at a fence corner with smooth wire going N & E. This corner has been accepted by land owners and other Surveys in the area."

Part C: "Found ½" rod-Porters-Set 1" x 32" iron pipe W/alumn.

DNR cap. Set carsonite Post.

4" W. Pine N78°E 23.68'

12" Maple N62°W 35.32'

18" Oak S18°W 16.89'

6" Maple S29°E 27.19'

SURVEY &  
REMONUMENTATION

JAN 14 1999

SECTION