

2361

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle County (County)	Located In: Bismarck	Corner Code #
1. Public Land Survey	T 34N R 4E	I-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

98 NOV 25 AM 11:14

Janet M. Sand
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James A. Beck, in a field survey on August 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8	1856 G.L.O. by Alfred Millerd	July 27, 1984	P.A. 74 (Land Corner Recordation) Certificate by
	"Set 1/4 Sec. post"		Ronald Bischer No.
	Y. Pine 12 N 81 E 71		22428
	Tamarack 10 S 64 W 58		Part A: "GLO NOTES"
			Part B: "Fd. 3/4" Pipe & old stake"
			Part C: 3/4" pipe
			N 39°E 22.50' Fe. Cor.
			N 70°E 16.42' 5" N. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8
Found 3/4" pipe and P.S. 15410 cap
all witnesses from 1984 recordation in good condition
and are marked with P.S. 15410 tags

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Walter J. Duran*
Date 7/3/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8
3/4" pipe and P.S. 15410 cap
Witnesses
N 39°E 22.50' Fe. Cor.
N 70°E 16.38' 5" N. Pine
N 77°W 24.55' 3" W. Pine
S 51°E 16.53' 6" N. Pine
new witness:
S 30°W 17.56', P.S. 21559 tag in 4" W. Pine

SURVEY &
REMONUMENTATION

JAN 14 1999

SECTION



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date October 5, 1998