

2365

329-601

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Presque Isle County (County) | Located in: Bismarck | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 34N R 4E | I-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

PRESQUE ISLE COUNTY
RECORDED

98 NOV 25 AM 11:15

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, James A. Beck, in a field survey on August 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-11 1856 G.L.O. by Alfred Millard
- "Set post Cor. of Secs 26, 27, 34 & 35"
- Y. Birch 15 N72 E 42
- B. Ash 15 S55 W 26

SEE REVERSE SIDE OF SHEET
FOR CONTINUATION PART "A"

SURVEY & REMONUMENTATION

JAN 14 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-11 found 1/2" iron rod and P.S. 15410 cap in monument box
- and the following 2 witnesses;
- N 70°W 142.50' P.S. 21559 tag in power pole
- N 2°W 74.10', P.S. 15410 tag in 14" Apple

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Norman J. ...*
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-11 1/2" iron rod and P.S. 15410 cap in monument box
- witnesses;
- N 70°W 142.50' P.S. 21559 tag in power pole
- N 2°W 74.10', P.S. 15410 tag in 14" Apple
- N 73°E 117.35' 21559 tag in power pole
- S 26°E 55.75' 21559 tag in 7" Cedar



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan
Remonumentation**

Bismarck Township, T34N, R4E

Corner code: I-11 Corner common to Sections 26, 27, 34, & 35

PART "A" CONTINUED

**September 26, 1978 P.A. 74 (Land Corner Recordation) Certificate by Delmer E. Porter
No. 15410**

Part A: (of certificate)

no entry

Part B: "Set in road centerline by single proportion"

Part C: ½" Rod & Cap in Mon. Box

N 70°W 144.50' P. Pole

N 02°W 74.10' 8" Apple

S 20°E 57.85' 4" Cedar

January 17, 1992 P.A. 132 Survey Certificate by James A. Beck No. 21559

Southeast Corner Section 27, T34N, R4E....

½" iron rod in monument box

Witnesses: N 70 deg W 144.50 ft., power pole

N 2 deg W 74.10 ft, 8" Apple

S 20 deg E 57.85 ft, 4" Cedar