

2366

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Presque Isle County, Located in: Bismarck, Corner Code # I-12, and survey types: 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec.

PRESQUE ISLE COUNTY
RECORDED

98 NOV 25 AM 11:15

Signature of Janet M. Lamb, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, James A. Beck, in a field survey on August 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration: I-12

1856 G.L.O. by Alfred Millerd
"Set qr. Sec. post"
Hemlock 12 S55E 15
Maple 10 N30W 7

SEE REVERSE SIDE OF SHEET
FOR CONTINUATION PART "A"

SURVEY &
REMONUMENTATION

JAN 14 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: I-12

found 1/2" iron and 15410 (Delmer E. Porter) cap at fence intersection and the following witnesses:
N 82°E 4.08 ft. 11" Maple ( P.S. 15410 tag)
N 72°W 8.31 ft. 10" Maple ( P.S. 15410 tag)
S 24°W 10.32 ft. 7" Maple ( P.S. 15410 tag )
S 58°E 16.08 ft. 7" Maple stem of 12"-7" ( P.S. 21559 tag)

Ratified by Peer Group
in accordance with P.A. 345
Chairman [Signature]
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: I-12

1/2" iron and 15410 (Delmer E. Porter) cap at fence intersection
Witnesses:
N 82°E 4.08 ft. 11" Maple ( P.S. 15410 tag)
N 72°W 8.31 ft. 10" Maple ( P.S. 15410 tag)
S 24°W 10.32 ft. 7" Maple ( P.S. 15410 tag )
S 58°E 16.08 ft. 7" Maple stem of 12"-7" ( P.S. 21559 tag)



Signed by [Signature]
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan  
Remonumentation**

**Bismarck Township, T34N, R4E**

**Date: September 18, 1998**

**Corner code: I-12      1/4 Corner common to Sections 34 and 35  
PART "A" CONTINUED**

**July 23, 1980 P.A. 74 (Land Corner Recordation) Certificate by Ronald R. Bischer  
No. 22428**

**Part A: (of certificate)  
Location conforms to GLO Notes  
Part B: Set at Fence Corners  
Part C: Set ½" Rod  
N 82°E 4.06' 9" Maple  
N 72°W 8.31' 9" Maple  
S 24°W 10.32' 5" Maple**

**August 22, 1995 P.A. 74 (Land Corner Recordation) Certificate by James A. Beck  
No. 21559**

**Part A: East 1/4 Corner Section 34, T34N, R4E  
Bismarck Township, Presque Isle County,  
Mi. Recorded by R. Bischer, July 23, 1980,  
"Set ½" iron at fence corners**

**Witnesses:  
N 82°E 4.08 ft. 9" Maple  
N 72°W 8.31 ft. 9" Maple  
S 24°W 10.32 ft. 5" Maple**

**Part B: East 1/4 Corner Section 34, T34N, R4E  
Bismarck Township, Presque Isle County,  
Mi. Recorded by R. Bischer, July 23, 1980,  
Found ½" iron and 15410 cap  
at fence corners.**

**Witnesses as recorded standing  
N 82°E 4.08 ft. 9" Maple  
N 72°W 8.31 ft. 9" Maple  
S 24°W 10.32 ft. 5" Maple**

**Part C: East 1/4 Corner Section 34, T34N, R4E  
Bismarck Township, Presque Isle County,  
Mi.  
Found ½" iron and 15410 cap**

**Witnesses:  
N 82°E 4.08 ft. 11" Maple  
N 72°W 8.31 ft. 10" Maple  
S 24°W 10.32 ft. 7" Maple  
S 58°E 16.08 ft. 7" Maple stem of 12"-7"**