

367

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle County (County)	Located in: Bismarck	Corner Code # I-13
1. Public Land Survey	T 34N R 4E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY  
RECORDED

98 NOV 25 AM 11:15

*Janice M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James A. Beck, in a field survey on August 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
I-13

1840 G.L.O. by George Hodgson  
"Set post corner Sections 34 and 35 in swamp"  
Balsam 6 N 49 E 8  
do 8 N 66 W 21

SEE REVERSE SIDE OF SHEET  
FOR CONTINUATION PART "A"

SURVEY &  
REMONUMENTATION

JAN 14 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
I-13

Found 1/2" iron & P.S. 21559 cap and the following witnesses:

N 33°E 27.36' 5" Maple  
S 53°E 48.23' 5" Cedar  
S 27°W 43.19' 6" Cedar  
N 59°W 54.20' 12" Spruce

Ratified by Peer Group  
in accordance with P.A. 345

Chairman *William J. Collins*  
Date 7/2/98

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
I-13

1/2" iron & P.S. 21559 cap and the following witnesses:

N 33°E 27.36' 5" Maple  
S 53°E 48.23' 5" Cedar  
S 27°W 43.19' 6" Cedar  
N 59°W 54.20' 12" Spruce  
all witnesses have P.S. 21559 tag



Signed by *James A. Beck*  
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan  
Remonumentation**

Bismarck Township, T34N, R4E

Land Corner History Sheet by James A. Beck P.S. 21559

Corner code: I-13      Corner common to Sections 34 and 35 on Town Line

**PART "A" CONTINUED**

- September 28, 1978      P.A. 74 (Land Corner Recordation) Certificate by  
Delmer E. Porter No. 15410  
Part A: no entry  
Part B: Found 5" pipe in Road CL and raised it with  
½" Rod. A local resident claims to have helped  
F. Loud set this corner.  
Part C: ½" rod  
N 33°E 27.32' 4" Maple  
S 57°E 40.04' 4" Cedar  
S 27°W 43.19' 5" Cedar
- April 23, 1981      P.A. 132 Certificate by Larry G. Beauregard No. 18654  
Recorded in Liber 240, Page 117  
"SE Cor. SEc. 34, 34/4"  
Ex. ½" bar (R)  
N 33°E 27.32' 4" Maple (R)  
S 57°E 40.04' 4" Cedar (R)  
S 27°W 43.19' 5" Cedar (R)
- August 22, 1995      P.A. 74 (Land Corner Recordation) Certificate by James A. Beck  
No. 21559  
Part A: "Southeast Corner Section 34, T34N, R4E, Bismarck  
Township, Presque Isle County, Mi.  
D. Porter FND 5" PIPE in road,  
raised with ½" iron  
Witnesses:  
N 33°E 27.32' 4" Maple  
S 57°E 40.04' 4" Cedar  
S 27°W 43.19' 5" Cedar  
Part B: "Southeast Corner Section 34, T34N, R4E, Bismarck  
Township, Presque Isle County, Mi.  
Found ½" iron and recorded witnesses standing.  
  
N 33°E 27.32' 4" Maple  
S 57°E 40.04' 4" Cedar  
S 27°W 43.19' 5" Cedar  
Part C: Southeast Corner Section 34, T34N, R4E, Bismarck  
Township, Presque Isle County, Mi.  
Found ½" iron set P.S. 21559 cap.  
  
N 33°E 27.36' 5" Maple  
S 57°E 40.04' 5" Cedar stump  
S 53°E 48.23' 5" Cedar  
S 27°W 43.19' 6" Cedar  
N 59°W 54.20' 12" Spruce