

2371

JAN 14 1999

LIBER 329 PAGE 611

SECTION

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle County (County)	Located in: Bismarck	Corner Code #
1. Public Land Survey	T 34N R 4E	J-7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

98 NOV 25 AM 11:16

Jane M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James A. Beck, in a field survey on August 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-7 1856 G.L.O. by Alfred Millerd
"Set quarter Section post"
W. Pine 12 N26E 29
W. Pine 12 S 21W 40

J-7 March 20, 1981 P.A. 74 (Land Corner Recordation) Certificate by
Delmer E. Porter No. 15410
Part A: (nothing); Part B: Set by Single Proportion
Part C: 1/2 Rod & RLS Cap
S 58°W 22.64' 6" Cedar; S64°W 10' Hunting Fe. Cor.
N31°E 5.42' 4" Black Ash; N64°W 28.65' 5" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 Found 1/2" iron and R.L.S. 15410 cap;
found all witnesses from March 20, 1981
recording
S 58°W 22.64' 6" Cedar Stump
S64°W 10', Fence . Cor. broken down
N31°E 5.42' 4" Black Ash
N64°W 28.65' 5" Cedar stump,
all above witnesses have RLS 15410 tags

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Thomas J. Quinn*
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-7 1/2" iron and R.L.S. 15410 cap;

Witnesses
S 58°W 22.64' 6" Cedar Stump
S64°W 10', Fence . Cor. broken down
N31°E 5.42' 4" Black Ash
N64°W 28.65' 5" Cedar stump,
all above witnesses have RLS 15410 tags
Set 2 additional witnesses: N 28°W 30.26', P.S. 21559 tag in 10" Cedar;
S 24°W 15.11', P.S. 21559 tag in 7" Black Ash



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date October 5, 1998