

373

SURVEY & REMONUMENTATION

JAN 14 1999

LIBR 329 REC 613

SECTION

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle County (County)	Located In: Bismarck	Corner Code #
1. Public Land Survey	T 34N R 4E	J-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY  
RECORDED

98 NOV 25 AM 11:16

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James A. Beck, in a field survey on August 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-11 1856 G.L.O. by Alfred Millerd  
" Set qr. Sec. post"  
Hemlock 12 N70W 5  
Hemlock 20 S45E 14

SEE REVERSE SIDE OF SHEET  
FOR CONTINUATION PART "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11  
Found 1/2" iron rod and P.S. 15410 cap in monument box  
Found 1 witness from previous recordations  
S 43°W 85.57', 6" Cedar (tag grown over) set P.S. 21559 tag

Ratified by Peer Group  
in accordance with P.A. 345

Chairman *William J. O'Connell*  
Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11  
1/2" iron rod and P.S. 15410 cap in monument box  
S 43°W 85.57', 6" Cedar P.S. 21559 tag  
N 9°W 36.25', P.S. 21559 tag in new power pole  
S 16°E 34.70', P.S. 21559 tag in new guy pole  
N 57°E 83.02', P.S. 21559 tag in 8" Tamarack



Signed by *James A. Beck*  
Surveyor's Michigan License No. 21559

Date October 5, 1998

**1998 Presque Isle County, State of Michigan  
Remonumentation**

Bismarck Township, T34N, R4E

**Corner code:** J-11 1/4 Corner Common to Sections 26 and 35

**PART "A" CONTINUED**

- September 26, 1978** P.A. 74 (Land Corner Recordation Certificate by Delmer E. Porter  
No. 15410  
Part A: No entry  
Part B: Set in Road CL by single proportion East & West  
Part C: ½" Rod & Cap in Mon. Box  
N09°W 31.75' P. Pole  
S 19°E 34.52' P. Pole  
S 43°W 85.57 6" Cedar
- November 13, 1980** P.A. 132 Survey Certificate Recorded Liber 239, Page 397  
By Delmer E. Porter No. 15410  
"S1/4 Cor. Sec. 26"  
½" Rod in Mon. Box  
N09°W 31.75' P. Pole  
S 43°W 85.57 6" Cedar  
S 19°E 34.52' P. Pole
- February 16, 1987** P.A. 132 Survey Certificate Recorded Liber 285, Page 645  
By Delmer E. Porter No. 15410  
½" Rod & Cap in Mon. Box  
N09°W 31.75' P. Pole  
S 19°E 34.52' P. Pole  
S 43°W 85.57 6" Cedar