

2374

SURVEY & REMONUMENTATION

JAN 14 1999

LIBER 329 PAGE 615

SECTION

1998 Presque Isle County State of Michigan Land Corner Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Presque Isle County
(County)

Located In: Bismarck Corner Code # J-13

1. Public Land Survey T 34N R 4E
T R
T R
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

PRESQUE ISLE COUNTY
RECORDED
98 NOV 25 AM 11:17
Janet M. Lamb
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on August 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 J-13 1840 G.L.O. By John Hodgson Set 1/4 Section post Hemlock 12 N15E 17 do 18 N51W 6
 J-13 September 28, 1978 P.A. 74 (Land Corner Recordation Certificate) by Delmer E. Porter No. 15410 (Recorded as J1 of T33N, R4E)
 Part A: No entry
 Part B: Found 1 1/2" Pipe 4' South of Road CL
 Part C: 1 1/2" Pipe; N32°W 40.25' P. Pole S62°W 47.70' 10" Cedar; S20°E 39.58' 8" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 J-13 Found 1 1/2" Pipe 4' South of Road CL, set 21559 cap in pipe found the following witnesses from Sep. 28, 1978 recordation; N32°W 40.25' P. Pole 15410 (Delmer E. Porter) tag S20°E 39.58' 9" Cedar, set P.S. 21559 tag (old tag grown over)

Ratified by Peer Group in accordance with P.A. 345
 Chairman *[Signature]*
 Date 7/2/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-13 1 1/2" Pipe 4' South of Road CL, with 21559 cap in pipe
 Witnesses:
 N32°W 40.25' P. Pole 15410 (Delmer E. Porter) tag
 S20°E 39.58' 9" Cedar, set P.S. 21559 tag (old tag grown over)
 Set 2 additional witnesses:
 S38°E 36.77', P.S. 21559 tag in 8" Cedar
 S 43°W 76.21', P.S. 21559 tag in 11" Cedar



Signed by *James A. Beck*
 Surveyor's Michigan License No. 21559

Date October 5, 1998