

2005

98 OCT 13 PM 3: 56

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u>	Located In:	Corner Code #
(County)		
<u>Bismark Township</u>	<u>T34N R 4E</u>	<u>K-5</u>
1. Public Land Survey	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald Bischer, in a field survey on 6-3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-5
1856 Alfred Millerd
Set wood post and 2 witnesses

1943+/- G.F. DeLaMater #2674
set 1/2" x48" bar in corner
left 2 witnesses

1981 Delmer Porter #15410
found 1/2" rod and 1 witness set 3 more witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5
Found 1/2" rod and set cap on top #22428

SURVEY &
REMONUMENTATION

JAN 14 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5
1/2" rod and cap #22428

N82°W	15.24'	5" Maple	O.W.
S09°W	32.13'	5" Maple	O.W.
N75°E	25.02'	10" Maple	
N18°E	26.42'	4" Maple	

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Norman J. Quinn*
Date 7/2/98

Signed by *Ronald R. Bischer*
Surveyor's Michigan License No. 22428

Date Sept. 20, 1998