

2016

1998 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

PRESQUE ISLE COUNTY
RECORDED

98 OCT 13 PM 3:58

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
Bismark Township	T 34N R 4E	L-5
1. Public Land Survey	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Jane M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald Bischer, in a field survey on 6-10, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5

1856 Alfred Millerd
Set wood post and 2 witnesses

April 6, 1982 Ronald Bischer #22428
1/2" rod located by Wilcox and Associates 1-12-77
found 1/2" rod and original bearing tree
also found 3 witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5
found 1/2" rod
set cap on 1/2" rod #22428

SURVEY &
REMONUMENTATION

JAN 14 1999

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5
1/2" rod and Cap #22428
N78°W 19.24' 6" Black Ash
N38°E 28.90' 6" Black Ash
S22°E 27.39' 8" Black Ash
N50°E 20.15' 10" Cedar stump (O.W.)
found old witnesses in poor shape

Ratified by Peer Group
in accordance with P.A. 345

Chairman *[Signature]*
Date 7/2/98

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date Sept. 28, 1988