

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

PRESQUE ISLE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 34NR 4E C-4
 T
 T
 T

2. Property Controlling in Section

S 7 T R 14
 S T R

3. Miscellaneous Property in Sec.

S T R
 S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on May 20, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5		●										
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-4

14

(NO EVIDENCE OF G.L.O. CORNER, B.T'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4

14

Reestablished the E1/4 Cor of Sec. 7 Midway and on line between found NE and SE corners of Sec. 7. Established the SE corner of the NE 1/4 of the SE 1/4 of Sec. 7, per standard BLM instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4

14

Set D.N.R. Mon.

24" R.Pine S34°E 62.30'
 12" Oak N63°W 91.22'
 20" Oak N20°W 106.04'
 N-S trail road 300'+/- East.

Set 5/8"x 3/4" rerod w/PS cap and carsonite post

8" R.Pine S28°W 64.68'
 8" Maple S63°W 12.16'
 5" Maple S82°W 37.89'



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 5-29-97