

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------|--------------------|
| <u>PRESQUE ISLE</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>J4NR 4E</u> | <u>B-5</u> |
| | T <u> R </u> | <u> </u> |
| | T <u> R </u> | <u> </u> |
| | T <u> R </u> | <u> </u> |
| 2. Property Controlling in Section | S <u>7</u> | T <u> R </u> |
| | S <u> </u> | T <u> R </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> R </u> |
| | S <u> </u> | T <u> R </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on May 19, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | • | • | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 B-5 16
 (NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 B-5 16
 Reestablished the S1/4 Corner of Sec. 7 on line between the found SW and SE corners of Sec. 7 and Prorated distance to U.S. G.L.O. runout. Center of E-W two track is 64' South. Established the SE corner of the SW1/4 of SE1/4 of Sec. 7 per standard BLM instructions. Center of E-W trail road is 4' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-5 16
 Set D.N.R. Mon and set carsonite post 11' South.
 Chisled X in stone N74°E 11.21'
 Chisled X in stone N04°E 19.79'
 Chisled X in stone N64°W 18.21'
 Fd. 1/2" Rerod South 4.18'

Set 5/8"x 32" Rerod w/PS cap.
 8" Oak N58°E 29.94'
 6" Oak N36°W 41.95'
 3" R.Pine S37°W 44.52'
 8" R.Pine S25°E 39.42'
 Set Carsonite post 15' North.



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 5-29-97