

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Presque Isle</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>4E</u>	<u>G-4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on July 3, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-4 G.L.O. Alfred Millerd D.S. 1856
 Set quarter section post
 Wit: Spruce 6" N55°E 22 links
 Spruce 7" S36°W 15 links

Delmer E. Porter L.S. #15410 L.C.R.C. Dec. 1998 L.329
 P. 876. Set 1/2" rod and cap #15410 by single proportionate.
 Wit: N19°W 16.90' 6" cedar, N40°E 27.90' 12" Cedar, S34°W 15.42' 10" Spruce, S55°E 46.42' 10" Spruce, 80'E of existing fence corner.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

G-4 Found 1/2" capped iron P.S. #33984

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 Found 1/2" capped iron #33984
 Wit: 8" Cedar N24°W 16.90'
 12" Cedar N40°E 27.88'
 10" Spruce S53°E 46.39'
 12" Spruce S77°W 15.41'



Signed by: Carl T Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 1-8-02