

93 DEC 20 PM 4:48

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Janet M. Sand
REGISTER OF DEEDS

For corners in

<u>PRESQUE ISLE</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>34N</u> R <u>2E</u>	<u>B-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **307** PAGE **880**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ronald R. Bischer, in a field survey on August 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1
Not Set in Original Survey
1979 - Ronald R. Bischer
Set 1/2" Rod & cap #15410 by single proportion
North 60.01' 6" Cedar
S51°W 12.48' Power pole
S05°W 137.13' 4" Apple tree

Recorded on Page 392, Land Recordation, June 8, 1979.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1
Found 1/2" Rod and Cap #15410
N02°W 59.89' 6" Cedar
S46°W 12.48' Power pole

SURVEY &
REMONUMENTATION

1993

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1
1/2" Rod and Cap #15410
N02°W 59.89' 6" Cedar
S46°W 12.48' Power pole
N08°W 90.02' 12" Cedar
S17°W 161.49' 6" Birch

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmer E. Porter*

Date December 7, 1993

*Witness tags and nails used.

Signed by Ronald R. Bischer

Date 12-13-93

Surveyor's Michigan License No. 22428

B-1 Corner, Section 6, Township 34N Range 2E

<u>Activity</u>	<u>Monument & Accessories</u>	<u>Notes</u>
Not set in Original Survey		
1979 Ronald R. Bischer #22428	Set $\frac{1}{2}$ " Rod by Single Proportion Set three witnesses Recorded on Page 392, Land Recordation, June 8, 1979	
1993 Remonumentation Ronald R. Bischer #22428	Found $\frac{1}{2}$ " Rod & cap #15410 N02°W 59.89' 6" Cedar found nail w/tag #15410 S46°W 12.48' Power pole found nail w/tag #15410 N08°W 90.02' 12" Cedar set nail w/tag #22428 S17°W 161.49' 6" Birch set nail w/tag #22428	

#5