

1993

COMMISSION

PRESQUE ISLE COUNTY
RECORDED

93 DEC 22 AM 10:01

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Janet M. Lamb
REGISTER OF DEEDS

For corners in

PRESQUE ISLE	Located In:	Corner Code #
1. Public Land Survey	T <u>34N</u> <u>2E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DELMER E. PORTER field survey on Dec. 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 GLO NOTES
JULY 14, 1855
10" CEDAR N 03° W 14 lks.
11" CEDAR S 03° E 5½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 DEC. 9, 1993
NOTHING FOUND
SET ½" ROD AND CAP #15410 AND
4" SQUARE BALSAM STAKE BY SINGLE PROPORTION

Ratified by Peer Group
in accordance with P.A. 345
Chairman Delmer E. Porter
Date December 18, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13
½" ROD & CAP #15410
S 42° W 20.02' 4" CEDAR
S 80° W 7.60' 6" SPRUCE
N 62° W 18.02' 5" CEDAR
N 23° W 33.98' 5" CEDAR
* NAILS & TAGS #15410 USED IN WITNESSES
PORTER'S SURVEY, P.C.



Signed by Delmer E. Porter

Date Dec 20 1993

Surveyor's Michigan License No. 15410

CORNER HISTORY RESEARCH SHEET

B-13

T34N,R2E ALLIS TOWNSHIP-NORTH PART,
PRESQUE ISLE COUNTY, MICHIGAN.

ACTIVITY MONUMENT & ACCESSORIES - COMMENTS

GLO Survey
July 14, 1855

10" Cedar N03°W 14 Links
11" Cedar S03°E 5 1/2 Links

Presque Isle
Remonumentation
Dec. 9, 1993

Set 1/2" Rod & Cap #15410
By single proportion
S42°W 20.02' 4" Cedar
S80°W 7.60' 6" Spruce
N62°W 18.02' 5" Cedar
N23°W 33.98' 5" Cedar

File

#5