

93 DEC 20 PM 4:49

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Janet M. Lamb
REGISTER OF DEEDS

For corners in

<u>PRESQUE ISLE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>2E</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **307** PAGE **894**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald R. Bischer, in a field survey on September 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5			●									
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-5	Due E 25.47' Fence corner
July 1855	1973 - Delmar E. Porter
Geo. H. Cannon set Wood Post	Found 1- $\frac{1}{4}$ " Pipe in Monument Box
14" Cedar S40°W 14 $\frac{1}{2}$ links	S89°40'E 74.45' 4" Concrete Monument
18" Hemlock N45°E 28 links	S87°26'W 76.42' Fence corner
1955 - Michigan State Highway Dept.	S30°05'W 153.85' Power pole
Set $\frac{1}{2}$ " Rod	Recorded on Page 38, Land
N57°W 41.94' 6" Cedar	Recordation, December 20, 1973.
N89°W 34.30' Fence corner	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5	Found $\frac{1}{2}$ " Rod and Cap #15410 inside 1- $\frac{1}{4}$ " Pipe in Monument Box.
S89°E 74.45'	4" Concrete Monument
S87°W 77.05'	Fence Corner
N81°E 75.65'	Fence Post
S30°W 153.85'	Power Pole

SURVEY &
REMONUMENTATION

1993

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5	$\frac{1}{2}$ " Rod and Cap #15410 in 1- $\frac{1}{4}$ " Pipe in Monument Box
S89°E 74.45'	4" Concrete Monument
S87°W 77.05'	Fence Corner
N81°E 75.65'	Fence Post
S30°W 153.85'	Power Pole

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmar E. Porter*
Date December 7, 1993

*Witness tags and nails used.

Signed by Ronald R. Bischer

Date 12-17-93

Surveyor's Michigan License No. 22428

C-5 Corner, Section 7,8,17&18, Township 34N Range 2E

<u>Activity</u>	<u>Monument & Accessories</u>	<u>Notes</u>
1855 Resurvey Geo. H. Cannon	Set Wood Post 14" Cedar S40°W 14½ links 18" Hemlock N45°E 28 links	
1955 MSHD	Set ½" rod Set 3 witnesses	(Not recorded)
1973 Delmar E. Porter #15410	Found 1¼" Pipe in Monument Box Set three witnesses. Recorded on Page 38, Land Recordation, December 20, 1973	
1993 Remonumentation Ronald R. Bischer #22428	Found ½" rod & cap #15410 in 1¼" pipe in monument box S89°E 74.45' 4" Concrete monument S87°W 77.05' Fence corner found nail w/tag #15410 N81°E 75.65' Fence post found nail w/MSHD tag S30°W 153.85' Power pole found nail w/tag #15410	

#3