

93 DEC 20 PM 4:49

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Janet M. Lamb
REGISTER OF DEEDS

For corners in

PRESQUE ISLE
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>34N</u>	R	<u>2E</u>	<u>E-6</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

LIBER **307** PAGE **912**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ronald R. Bischer, in a field survey on September 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6	S36°E 38.89' 24" Maple
1855 Resurvey - Geo. H. Cannon (July)	N38°E 41.30' 20" Maple
Set Wood Post	Recorded on Page 164, Land Recordation, 11/24/76.
7" Beech N54°W 30½ links	1978 - Delmar E. Porter (Remonumentation)
12" Beech S48°E 26 links	Found ½" Rod, set Monument Box
1976 - Ronald R. Bischer	Used 3 Bischer witnesses from 1976.
Set ½" Rod by Single Proportion	Recorded on Page 295, Land
N82°W 27.92' 30" Maple	Recordation, September 29, 1978.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6
 Found ½" Rod, Monument box gone
 N82°W 27.92' 32" Maple
 N38°E 41.30' 22" Maple
 S36°E 38.89' 26" Maple

SURVEY &
 REMONUMENTATION

Set Cap #22428 on ½" Rod.

1993

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6
 ½" Rod and Cap #22428
 N82°W 27.92' 32" Maple
 N38°E 41.30' 22" Maple
 S36°E 38.89' 26" Maple
 N24°W 69.89' 29" Maple

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Delmar E. Porter*
 Date December 7, 1993

*Witness tags and nails used.

Signed by Ronald R. Bischer

Date 12-13-93

Surveyor's Michigan License No. 22428

E-6 Corner, Section 16, 17, Township 34N Range 2E

<u>Activity</u>	<u>Monument & Accessories</u>	<u>Notes</u>
1855 Resurvey Geo. H. Cannon	Set Wood Post 7" Beech N54°W 30½ links 12" Beech S48°E 26 links	
1976 Ronald R. Bischer #22428	Set ½" Rod by Single Proportion Set three witnesses. Recorded on Page 164, Land Recordation, November 24, 1976.	
1978 Remonumentation Delmar E. Porter #22428	Found ½" rod, set monument box Three witnesses. Recorded on Page 295, Land Recordation, September 29, 1978.	
1993 Remonumentation Ronald R. Bischer #22428	Found ½" Rod - mon. box gone N82°W 27.92' 32" Maple found nail w/tag #15410 N38°E 41.30' 22" Maple found nail w/tag "15410 S36°E 38.89' 26" Maple found nail w/tag "15410 N24°W 69.89' 29" Maple set nail w/tag #22428	

#5'