

*Janet M. Lamb*  
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

PRESQUE ISLE  
(County)

Located In:

Corner Code #/

1. Public Land Survey	T	<u>34N</u>	R	<u>2E</u>	<u>F-3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

LIBER **307** PAGE **916**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3					●							
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Ronald R. Bischer, in a field survey on September 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-3  
 1855 Resurvey - Geo. H. Cannon (July) S40°E 105.18' 6" Birch  
 Set Wood Post S08°W 4.45' 9" Elm  
 16" Sugar S38°E 24 links Recorded on Page 30, Land  
 13" Sugar N67°W 33 links Recordation, October 25, 1973.  
 1973 - Delmar E. Porter  
 Found 1/2" Rod  
 N85°E 46.44' 16" Ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3  
 Found 1/2" Rod and Cap #15410  
 N85°E 46.44' 24" Ash  
 S38°E 105.38' 10" Birch  
 S33°W 4.45' 9" Elm



SURVEY &  
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3  
 1/2" Rod and Cap #15410  
 S38°E 105.38' 10" Birch  
 N85°E 46.44' 24" Ash  
 S33°W 4.45' 9" Elm  
 N26°E 20.75' 5" Ironwood

\*Witness tags and nails used.

Ratified by Peer Group  
in accordance with P.A. 345

Chairman Delmar E. Porter

Date December 7, 1993

Signed by Ronald R. Bischer

Date 12-13-93

Surveyor's Michigan License No. 22428

F-3 Corner, Section 4, 9, Township 34N Range 2E

<u>Activity</u>	<u>Monument &amp; Accessories</u>	<u>Notes</u>
1855 Resurvey Geo. H. Cannon	Set Wood Post 16" Sugar S38°E 24 links 13" Sugar N67°W 33 links	
1973 Delmar E. Porter #15410	Found ½" Rod Three witnesses. Recorded on Page 30, Land Recordation, October 25, 1973.	
1993 Remonumentation Ronald R. Bischer #22428	Found ½" Rod & cap #15410 N85°E 46.44' 24" Ash found nail w/tag #15410 S38°E 105.38' 10" Birch found nail w/tag #15410 S33°W 4.45' 9" Elm found nail w/tag #15410 N26°E 20.75' 5" Ironwood set nail w/tag #22428	

#3