

PRESQUE ISLE COUNTY
RECORDED

93 DEC 20 PM 4:50

Janet M. Lamb
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>PRESQUE ISLE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>2E</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 307 PAGE 958

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald R. Bischer, in a field survey on September 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1

Not set in Original Survey
1978 - Delmar E. Porter (Remonumentation)
Found 1/2" Rod and Cap #15410 set by single proportion - Replaced 1/2" Rod with Concrete Monument w/Brass Cap
N45°E 27.72' 4" Aspen
N06°W 69.95' 10" Maple

N48°W 78.45' 18" Maple
Recorded on Page 319, Land Recordation, November 29, 1978.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1

Found Presque Isle County Remonumentation Monument
N09°W 69.95' 12" Maple
N49°W 78.45' 18" Maple
N45°E 27.72' 4" Aspen
witness is broken stub 4' tall

SURVEY &
REMONUMENTATION

1893

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1

Presque Isle County Remonumentation Monument
N09°W 69.95' 12" Maple
N49°W 78.45' 18" Maple
N34°E 89.95' 20" Maple
S03°W 18.27' Fence corner

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmar E. Porter*

Date December 7, 1993

*Witness nails and tags used.

Signed by Ronald R. Bischer

Date 12-13-93

Surveyor's Michigan License No. 22428

J-1 Corner, Section 2, Township 34N Range 2E

<u>Activity</u>	<u>Monument & Accessories</u>	<u>Notes</u>
Corner not set in Original Survey		
1978 Delmar E. Porter #15410	Found $\frac{1}{2}$ " Rod set by Porter's Survey, replaced with Concrete Monument w/Brass Cap Three witnesses. Recorded on Page 319, Land Recordation, November 29, 1978	
1993 Remonumentation Ronald R. Bischer #22428	Found Concrete Monument w/Brass Cap N09°W 69.95' 12" Maple found nail w/tag #15410 N49°W 78.45' 18" Maple found nail w/tag #15410 N45°E 27.72' 4" Aspen witness is broken stub 4' tall N34°E 89.95' 20" Maple set nail w/tag #22428 S03°W 18.27' Fence corner set nail w/tag #22428	

#5