

93 DEC 22 AM 10:04

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Janet M. Lamb*  
REGISTER OF DEEDS

For corners in

Presque Isle  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 34N R 2E      J-9  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   |    |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

Delmer E. Porter in a field survey on Sept. 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9  
GLO Notes  
July 11, 1993  
Sugar 9" N45° E 25 Links  
Sugar 20" S43W 9 Links

J-9  
P.A. filing by Ronald R. Bischer  
LS #22428, Oct. 19, 1990, Page 815  
Land Corner Records  
Found 1/2" Rod & Cap #15410  
N55° W 60.77' 4" Elm  
N56° E 67.65' 7" Maple  
S15° W 70.45' 6" Lynn

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Sept. 11, 1993  
Found 1/2" Rod & Cap #15410  
N49° W 60.83' 4" Elm  
N62° E 67.75' 9" Maple  
Direct testimony by Ronald R. Bischer revealed that the corner was set by single proportion approximately 1970.

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman Delmer E. Porter  
Date December 18, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9  
1/2" Rod & Cap #15410  
N49° W 60.83' 4" Elm  
N62° E 67.75' 9" Maple  
S50° E 66.43' 4" Elm  
S44° W 63.90' 10" Aspen

\*Nails & tags #15410 used on witnesses.

Porter's Survey P.C.



Signed by Delmer E. Porter

Date Dec 20, 1993

Surveyor's Michigan License No. 15410

# CORNER HISTORY RESEARCH SHEET

J-9

T34N,R2E ALLIS TOWNSHIP-NORTH PART,  
PRESQUE ISLE COUNTY, MICHIGAN.

## ACTIVITY      MONUMENT & ACCESSORIES      -      COMMENTS

|   |   |   |
|---|---|---|
| GLO Survey<br>July 11, 1855   | Sugar 9" N45°E 25 Links<br>Sugar 20" S43°W 9 Links  |   |
| Act 132 Survey by<br>Delmer E. Porter #15410<br>Recorded Nov. 30, 1984<br>SUR#12-84 File#34R2146<br>Liber 255, Page 408 | FD. 1/2" Rod<br>N56°E 67.78' 5" Maple<br>S15°W 70.37' 8" Basswood<br>N53°W 60.57' 8" Elm  | Set by S.P.<br>- 1968 -<br>AS PER<br><u>Ron Bischer</u> |
| Act 74 Filing by<br>Ronald R. Bischer,<br>#22428, Oct. 19, 1990<br>Page 815, Corner<br>Recordation                      | Fd. 1/2" Rod & Cap #15410<br>Left Same<br>N55°W 60.77' 4" Elm<br>N56°E 67.65' 7" Maple<br>S15°W 70.45' 6" Lynn  |   |
| Remonumentation<br>Sept. 11, 1993   | FD. 1/2" Rod & Cap #15410<br>N49°W 60.83' 4" Elm<br>N62°E 67.75' 9" Maple<br>Left Same<br>N49°W 60.83' 4" Elm<br>N62°E 67.75' 9" Maple<br>S50°E 66.43' 4" Elm<br>S44°W 63.90' 10" Aspen |   |

~~#5~~