

1993
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PRESQUE ISLE COUNTY
RECORDED

93 DEC 20 PM 4:47

Janet M. Lamb
REGISTER OF DEEDS

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>2E</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **307** PAGE **866**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James A. Beck, in a field survey on August 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13
1855: Original monumentation by Geo H. Cannon in Government Resurvey of T34N-R2E. Set wood post and referenced:
14" Elm N44°E 13 Links
8" Sugar S24°W 10 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13
1993: Found a 2" pipe as noted by Delmer E. Porter, P.S. 15410, in recorded surveys. (Recorded Aug. 31, 1977, L 219, P 12, & L219, P 14, Presque Isle County Records. Found no recorded witnesses.

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmer E. Porter*

Date *December 7, 1993*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13
1993: 1/2" iron rod and cap P.S. 21559 in 2" pipe. Corner lies at centerline of road to North and 3' Southerly of East-West road centerline.
Witnesses:
N34°W 50.92' Power Pole (tag 21559)
S49°W 48.06' Guy Pole (tag 21559)
N42°E 32.55' Near Face of Road Sign Base Pipe
N70°E 89.64' Power Pole (tag 21559)



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date *12-14-1993*

Corner History Research Sheet

SE Corner, Section 36, T34N-R2E, Presque Isle County
(M-13)

Activity	Monument and Accessories	Comments
1855: Government Resurvey by Geo H. Cannon.	Set wood post and referenced: 14" Elm N44°E 13 Links 8" Sugar S24°W 10 Links	
August, 1971: From Corner Card furnished by Delmer E. Porter.	Described corner and witnesses in notes. 2" pipe. Referenced: S11°E 38.81' 7" Elm S27°W 53.21' 10" Elm N39°E 91.71' 6" Elm	
July, 1977: Surveys by Delmer E. Porter.	Noted corner in surveys. Found 2" pipe. Referenced: N39°E 91.71' 5" Elm S11°E 38.81' 7" Elm S27°W 53.21' 10" Elm	Recorded Aug. 31, 1977, L 219, P 12, & L 219, P 14, Presque Isle County Records.
August, 1993: Remonumentation by James A. Beck.	Found a 2" pipe at centerline of road to North and 3' Southerly of centerline of East-West Road. Set a 1/2" iron rod and cap P.S. 21559 in pipe. Established all new witnesses. Referenced: N34°W 50.92' Power Pole (Set Tag P.S. 21559) S49°W 48.06' Guy Pole (Set Tag P.S. 21559) N42°E 32.55' Near Face Road Sign Base Pipe N70°E 89.64' Power Pole (Set Tag P.S. 21559)	

December 2, 1993

James A. Beck, P.S. 21559