

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 318 PAGE 622

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T34N R 5E	A-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:24

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman J. Quaine in a field survey on Dec 8, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-5	1856	1856	1856
1840	Re-established Twp.	Correcting Bet.	Correcting Bet.
Twp lines run	Line by Alfred Millerd	Sec 7&18. Millerd	Sec 12&13, T34N
by John Hodgson	Reset all corners	makes ref. to new B.T.	R4E
Deputy Surveyor	on Township Line	Hemlock 10 S52E 10'	A. Millerd
No Descript. of	Set Post cor of Sec.		Hemlock 12 N75W
corner given	12&13, T34N, R4E		39 Links
	Y Birch 14 S5W 20		
	Cedar 12 N40E 7		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5		
December 8, 1995	Fd. Conc Mon. No Cap	
Norman J. Quaine LS#33984	in "Gate Line"	
Porter's Survey P.C.	5' S of Two Track C/L	
1996 P.I. Co. State	N31°E 24.72' 6" Maple	
Remonumentation	S34°W 27.56' 10" Cedar	
	N41°W 30.71' 10" Maple	

LCRC
October 7, 1979
Delmer E. Porter
LS #15410
Fd. 1" Pipe
Set Conc Mon w/brass cap
N31°E 24.51' 4" Maple
S34°W 27.42' 10" Cedar
N41°W 30.52' 6" Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5
Left Conc Mon No Cap
in "Gate Line"
5' S of Two Track C/L
N31°E 24.72' 6" Maple
S34°W 27.56' 10" Cedar
N41°W 30.71' 10" Maple
S48°E 34.97' 4" Maple

*Witness tags & nails.

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date 5/22/96

Porter's Survey P.C.
Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date MAY 29, 1996