

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T 34N R 5E	A-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:24

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Norman J. Quaine, in a field survey on January 26, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A-6
 1840
 Township lines run by John Hodgson Deputy Surveyor
 No description given
 1856
 Re-Established Twp. line by Alfred Millerd
 Reset all township corners on the west line
 Set Quarter section post
 Cedar 12 N50E 11
 Spruce 8 S70W 12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-6
 January 26, 1996
 Norman J. Quaine
 P.S. #33984, Porter's Survey P.C.
 1996 P.I. Co. State Remonumentation
 Fd. No evidence as to corner's position.
 Set 1/2" Rod & Cap #33984 by Single Proportion

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-6
 Left 1/2" Rod & Cap #33984
 S51°E 8.89' 14" Aspen
 S12°E 27.04' 10" Aspen
 N68°W 47.96' 5" Balsam
 N22°W 41.58' 6" Balsam

*Witness tags & nails used.

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Norman J. Quaine*
 Date 5/22/96

Porter's Survey P.C.
 Signed by Norman J. Quaine Date MAY 29, 1996
 Surveyor's Michigan License No. 23984