

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T34N R 5E	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY RECORDED

96 JUN -4 AM 11:24

Janet M. Lamb REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SECTION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman J. Quaine, in a field survey on January 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- A-7 1856 Millerd Witnessed LCRC
  - 1840 Re-Est. Twp. line while closing July 19, 1979
  - Twp. lines run by by Alfred Millerd from East Delmer E. Porter
  - John Hodgson reset all corners LS#15410
  - Deputy Surveyor on Twp. line N87° 54'E 11.14 Cedar 5
  - Tam 14 S47W 17 Set post corner of Tam 10 S15E 16
  - B. Ash 10 S13E 31 Sec 13 & 24 Do 8 N43E 69
  - Spruce 8 N25W 32
  - Tamarack 12 S60W 8

Fd 2 OBTs & set cor position from them  
Conc Mon & Brass Cap  
N81°E 13.62' 2" Birch  
S16°E 65.99' 4" Birch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7  
January 24, 1996 Fd. Conc. Mon/Brass Cap  
Norman J. Quaine N81°E 13.66' 4" Birch  
PS #33984, Porter's S60°W 5.3' OBT Stump  
Survey P.C.  
1996 P.I. Co. State  
Remonumentation

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7  
Left Conc. Mon/Brass Cap  
N81°E 13.66' 4" Birch  
S60°W 5.3' OBT Stump  
S82°E 36.24' 6" Birch  
S17°E 13.54' 4" Birch  
S79°W 77.87' 7" Balsam

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman [Signature]  
Date 5/22/96

\*Witness tags & nails.

Porter's Survey P.C.

Signed by Norman J. Quaine Date MAY 22, 1996

Surveyor's Michigan License No. 33984