

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T34N R 5E	A-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:24

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on Dec. 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9	1856	1856	Nov. 30, 1971
1840	Re-established	Closing from the	Survey recorded in
Twp. lines run	Twp line by	East Between Sec.	Liber 196, Pg 399 by
by John Hodgson	Alfred Millerd	19 & 30	Delmer E. Porter
Deputy Surveyor	Deputy Surveyor	Cedar 5 N5E 25	1/2" Rod LS#15410
No Description given	Set Post at cor of	Spruce 9 S60E 11	P. Pole N30°W 50.83'
	Sec 24&25, T34N, R4E		7" Cedar N35°W 77.11'
	Cedar 5 N32W 12		Cor F Post due E 83.81'
	Cedar 10 S10W 2		NOTE: Assumed typo error
	Old Corner not Rd		on FE Cor, Should be

33.81'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9
December 8, 1995
Norman J. Quaine PS#33984
Porter's Survey P.C.
1996 P.I. Co. State
Remonumentation
Fd. 1/2" Rod in Mon Box
N30°W 49.66' P. Pole
N35°E 76.97' 8" Cedar
N15°E 79.25' 8" Elm

LCRC
Sept. 29, 1978
Delmer E. Porter
LS#15410
1/2" Rod in Mon Box
N30°W 49.57' P. Pole
N35°E 76.90' 7" Cedar
Due East 33.81' FE Cor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9
Left 1/2" Rod in Mon Box
Int. of road
N30°W 49.66' P. Pole
N35°E 76.97' 8" Cedar
N48°E 54.17' Guy Pole
N15°E 79.25' 8" Elm

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date 5/22/96

*Witness tags & nails.

Porter's Survey P.C.

Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date May 29, 1996