

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:25

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Presque Isle Located In: Corner Code #
1. Public Land Survey T34NR 5E A-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. Recorded Plat
5. Private Claims

Norman J. Quaine in a field survey on Dec. 11 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Numbers 6-36 are placed in the grid cells.

A. Description of original monument and accessories and/or subsequent restoration:

A-11 1856 1856
1840 Re-est. Twp. line Closing from E.
Twp lines run by Alfred Millerd Bet. Sec 30&31
by John Hodgson Deputy Surveyor Alfred Millerd
Deputy Surveyor Reset all Twp cors. Deputy Surveyor
Beech 8 N60W 11 Set post cor of Sec Hemlock 12 S25E 31
Do 10 N15E 24 25&36 T34N R4E Beech 12 N67E 32
Hemlock 10 S66W 16
Beech 12 N53W 30

June 14, 1972, Survey
Rec. in Liber 198, Pg 291
Delmer E. Porter LS#15410
1 1/4" Pipe
N20°W P. Pole 97.95'
N35°W FE Cor 37.65'
N45°E 4" Pine 51.51'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11
December 11, 1995 Fd. Conc Mon/Brass Cap
Norman J. Quaine PS#33984 S76°E 41.94' 8" N. Pine
Porter's Survey P.C. N70°E 45.67' 10" N. Pine
1996 P.I. Co. State
Remonumentation

June 14, 1972, Survey
Rec. in Liber 198, Pg 293
Delmer E. Porter LS#15410
1 1/4" Pipe
N20°W P Pole 97.95'
N35°W Fe Cor 37.65'
N45°E 4" Pine 51.51'

Ratified by Peer Group
in accordance with P.A. 345
Chairman [Signature]
Date 5/22/96

July 11, 1972 Sur Rec. Liber 198
Pg 545, Donald A. Marlatt LS#18660
NW Cor. Sec 31, T34N, R5E
Existing 1" Pipe

C. Description of monument for corner and accessories established to perpetuate

A-11
Left Conc Mon/Brass Cap
S76°E 41.94' 8" N. Pine
N70°E 45.67' 10" N. Pine
S57°W 11.11 10" Aspen
S39°E 57.27' 6" N. Pine
P. Pole was replaced

locating the position of the corner:
Feb. 22, 1973 Sur Rec. in Liber 200
Pg 864, Delmer E. Porter LS#15410
1 1/4" Pipe, N20°W P. Pole 97.95'
N35°W FE Cor 37.65'
N45°E 4" Pine 51.51'
Nov. 29, 1978, LCRC Delmer E. Porter LS#15410
Fd 1 1/4" Pipe & replaced w/conc mon
w/brass cap, N15°W 97.95' P. Pole
N70°E 45.76' 5" N. Pine, S76°E 41.85' 3" N. Pine

*Witness tags & nails.

Porter's Survey P.C.

Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date May 29 1996