

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:25

Janet M. Lamb
REGISTER OF DEEDS

For corners in

Presque Isle Located In: Corner Code #
(County)

1. Public Land Survey T³⁴N R 5E A-12
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SURVEY &
DOCUMENTATION

JAN 22 2001

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman J. Quaine in a field survey on Dec. 8, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-12	1856	June 14, 1972	Feb. 22, 1973 Surve
1840	Re-established Twp.	Sur Rec. in Liber	Rec. Liber 200 Pg86
Twp lines run	line by Alfred Millerd	198, Pg 293	Delmer E. Porter
by John Hodgson	Deputy Surveyor	Delmer E. Porter	LS#15410
Deputy Surveyor	All Twp. corners reset	LS#15410	1/2" Pipe
Beech 8 N38W 9 1/2	Set Quarter sec. post	1/2" Pipe	N30°W P Pole 59.90'
Do 14 N49E 20	Hemlock 10 N38E 11	N30°W P. Pole 59.90'	Due W Conc Mon 33.1
	Hemlock 14 S45W 19	Due W Conc Mon 33.15'	N80° E 6" Cedar
		N80° E 6" Cedar 37.25'	37.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

A-12		Sept. 29, 1978, LCRC
December 8, 1995		Delmer E. Porter LS#15410
Norman J. Quaine PS#33984	Fd 1/2" Rod in Mon Box	1/2" Pipe & put in Mon Bo
Porter's Survey P.C.	Put Cap #33984 On	N30°W 59.90' P. Pole
1996 P.I. Co. State	N30°W 60.05' P. Pole	N80°E 37.25' 6" Cedar
Remonumentation	N32°E 82.71' 6" Maple	Due W 33.15' Conc Mon
	N80°E 39.20' 6" Cedar	
	S22°E 55.29' 16" Aspen	
	N87°W 33.15' Conc Mon	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12		March 16, 1989, Sur. Rec
Left 1/2" Rod & Cap #33984 in Mon Box		in Liber 285, Pg 644
N30°W 60.65' P. Pole		Delmer E. Porter LS#15410
N32°E 82.71' 6" Maple		1/2" Pipe in Mon Box
N80°E 39.20' 6" Cedar		N30°W 59.90' P. Pole
S22°E 55.29' 16" Aspen		N80°E 37.25' 6" Cedar
N87°W 33.15' Conc Mon		West 33.15' Conc Mon

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date 5/22/96

*Witness tags & nails used.

Porter's Survey P.C.
Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date MAY 29, 1996