

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T34NR 5E	A-13
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:25

Jenct M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman J. Quaine in a field survey on Dec. 8, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13 1856
1840 Re-established Twp.
Twp. line run lines by Alfred Millerd
by John Hodgson Remeasured south line
Deputy Surveyor of Sec 31, T34N, R5E
Six Mile Post at Inters. No Description of
T's 33&34N, R4&5E corner given
Cedar 24 S81W 134 Assumed to be the
Do 12 N70E 1.50 same as Hodgsons

Private Records, 1958
R.S. Scott & Assoc.
Fd 1" Pipe & 4"x4" Stake
N45°W 45.16' FE cor
N45°E 43.6' FE Cor

LCRC, Sept 19, 1978
Delmer E. Porter LS#15410
1/2" Rod in Mon box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
December 8, 1999
Norman J. Quaine PS#33984
Porter's Survey P.C.
1996 P.I. Co. State
Remonumentation
Fd. 1/2" Rod & Cap #15410 in Mon Box
S32°W 70.80' P. Pole

N40°W 45.63' FE Cor
N58°E 51.50' FE Cor
S34°W 65.85' P. Pole

March 16, 1989, Survey Recorded
in Liber 285, Pg. 644
Delmer E. Porter LS#15410
1/2" Rod in Mon Box
N40°W 45.63' FE Cor
N58°E 51.50' FE Cor
S34°W 65.85' P. Pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13
Left 1/2" Rod & Cap #15410 in Mon Box
S32°W 70.80' P. Pole
N32°W 52.28' P. Pole
N50°E 60.58' FE cor
S48°E 75.00' Sign Post

March 16, 1994
LCRC, Norman J. Quaine #33984
1/2" Rod & Cap #15410 in Mon Box
S32°W 70.80' P. Pole
N32°W 52.28' P. Pole
N50°E 60.58' FE Cor
S45°E 75.00' Wooden Sign Post

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmer E. Porter*

*Witness tags & nails. Date 5/22/96

Porter's Survey P.C.
Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date MAY 29 1996