

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>5E</u>	<u>B-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:25

Jana M. Stamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Norman J. Quaine in a field survey on December 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1	1840	1856	Feb. 16, 1976
Twp. lines run	by John Hodgson	Re-examination of	LCRC
Deputy Surveyor	Set 1/4 Sec. Post	North Townline	Delmer E. Porter LS#15410
Lynn 16 N21W 10	Beech 17 N56E 23	Alfred Millerd	Found 1/2" Rod
		Deputy Surveyor	S30°W 48.41' 4" Cedar
		West on South side	S17°E 45.09' 4" Cedar
		Sec 31 T35N R5E	
		40.00 old Quarter Cor	
		No new witnesses given	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1	December 8, 1995	Found 1/2" Rod
Norman J. Quaine	P.S.#33984, Porter's	Put Cap #33984 on
Survey P.C.	1996 P.I. Co. State	S25°E 45.21' 5" Cedar
Remonumentation		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1
 Left 1/2" Rod & Cap #33984
 in C/L Heythaler Road
 S25°E 45.21' 5" Cedar
 S28°W 48.24' 8" Cedar
 N30°E 67.80' 6" Aspen
 N47°E 77.77' 6" Cedar

Ratified by Peer Group
 in accordance with P.A. 345

Chairman *Delmer E. Porter*

Date 5/22/96

*Witness tags & nails .

Porter's Survey P.C.

Signed by *Norman J. Quaine* Date May 29, 1996
 Surveyor's Michigan License No. 33984