

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>34N</u> R <u>5E</u> | <u>B-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:25

Jane M. Lamb

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on December 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-3		
July 19 +/-, 1856	Sept. 29, 1978	Nov. 9, 1979
Sec. Subdivision by Alfred Millerd	LCRC	LCRC
Deputy Surveyor	Delmer E. Porter	Delmer E. Porter LS#15410
Set Quarter Sec. Post	LS #15410	Fd 1/2" Rod/replaced with conc.
Hemlock 12 N60W 28	Fd. Old stake and 1/2" Rod in Rd. C/L	Mon with brass cap
Beech 11 S52E 22	Due N 32.40' FE Cor	Due N 32.40' FE Cor
	S35°E 35.57' 3" Cedar	S35°E 35.57' 3" Cedar
	Due S 30.42' FE Cor	Due S. 30.42' FE Cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3	
December 8, 1995	Fd. Conc Mon.
Norman J. Quaine	Put cap #33984 on
PS#33984, Porter's Survey P.C.	S03°W 32.62' P. Pole (Beck's)
1996 P.I. Co. State Remonumentation	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3
Left Conc Mon & Cap #33984 in C/L Rd.
S03°W 32.62' P. Pole
S07°W 30.51' FE Cor
N20°W 84.43' SE cor House
N14°W 106.94' NE Cor House

*Witness tags & nails.

Porter's Survey P.C.

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmer E. Porter*

Date 5/22/96

Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date MAY 29 1996