

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 34N R 5E	B-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY  
RECORDED

96 JUN -4 AM 11:25

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	•												
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine, in a field survey on December 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court, of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5	Nov. 9, 1979	May 29, 1990
1856	LCRC, Delmer E. Porter	Survey recorded Liber 302, Pg. 745
Subdivision by	LS#15410	By Ronald R. Bischer LS#22428
Alfred Millerd	Fd 1" Pipe/replaced w/	N 1/4 - Conc Mon
Deputy Surveyor	Conc Mon & Brass cap	N31°E 24.51' 4" Maple
Set Quarter Sec Post	N16°E 33.05' 2" Apple	N41°W 30.52' 6" Maple
Sugar 4 S15W 22	N13°W 38.02' FE Post	S34°W 27.42' 10" Cedar
Sugar 4 N75E 23	N40°W 51.93' FE Post	

June 21, 1995  
LCRC, James A. Beck  
LS#21559

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5	Fd. Conc Mon/Brass Cap	Fd Conc Mon w/brasscap
December 8, 1995	10' South of Rd. C/L	N18°E 55.27' 5"W.Pine
Norman J. Quaine	S58°E 31.47' 4" Maple (Beck's)	N48°E 62.00' 4"W.Pine
LS#33984, Porter's	S33°E 28.83' 5" Maple (Beck's)	S60°E 31.40' 5" Maple
Survey P.C.	N21°E 55.38' 4" W. Pine (Beck's)	S36°E 28.82' 8" Maple
1996 P.I. Co. State	N51°E 62.14' 4" W. Pine (Beck's)	
Remonumentation		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5  
Left Conc Mon/Brass Cap  
10' South of C/L Road  
S58°E 31.47' 4" Maple  
S33°E 28.83' 5" Maple  
N21°E 55.38' 4" W. Pine  
N51°E 62.14' 4" W. Pine

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman Delmer E. Porter  
Date 5/22/96

\*Witness tags & nails.

Porter's Survey P.C.  
Signed by Norman J. Quaine Date May 29, 1996  
Surveyor's Michigan License No. 33984