

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T 34N R 5E	B-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:26

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine, in a field survey on December 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 B-13 1856 March 26, 1981
 1840 Remeasurement of LCRC
 Twp. lines run South Side Sec 31 Ronald R. Bischer LS#22428
 by John Hodgson T34N, R5E, by Porter's Survey P.C.
 Deputy Surveyor Alfred Millerd Fd. Fredrick Loud's Cor - 190' South
 Set 1/4 Section Post Deputy Surveyor Also Fd 1/2" Rod. Placed in Rd E 20'
 Beech 14 N17W 17 Measured 40.00 chains North & 20' E of Loud's Corner
 Do 8 N75E 50 for East 1/2 of S line Set 1/2" Rod at S.P. This fits 4000'
 Assumed to be the same of the N-S 1/4 line Road E
 as Hodgsons S53°W 60.22' P. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 B-13 N65°E 48.57' 24" Tw. Maple
 December 8, 1995 Fd. 1/2" Rod & Cap #15410 S11°W 73.33' 7" Apple
 Norman J. Quaine N65°E 48.65' 28" Twin Maple
 P.S.#33984, Porter's S11°W 73.43' 10" Apple
 Survey P.C. S53°W 60.21' P. Pole
 1996 P.I. Co. State 20' W & 190' N of Rd. C/L Int.
 Remonumentation

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-13
 Left 1/2" Rod & Cap #15410
 20' W & 190' N of Rd. Int. C/L
 N65°E 48.65' 28" Twin Maple
 S11°W 73.43' 10" Apple
 S53°W 60.21' P. Pole
 N57°E 74.42' 8" W. Pine

*Witness tags & nails.

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmu & Porter*
Date 5/22/96

Porter's Survey P.C.
Signed by Norman J. Quaine Date MAY 29, 1996
Surveyor's Michigan License No. 33984