

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 34N R 5E	C-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

PRESQUE ISLE COUNTY  
RECORDED

96 JUN -4 AM 11:26

*Jane M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Norman J. Quaine, in a field survey on December 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-2	May 5, 1948	April 13, 1988
1856	Survey by Donald A. Marlatt	LCRC
Section Subdivision by Alfred Millerd Deputy Surveyor	(Not Recorded)	James A. Beck LS#21559
Set Quarter Sec. Post Beech 11 N45W 6 Beech 12 S55E 24	No physical corner Description given on face of survey	Fd. 3"X3" Wooden Stake & 1/2" Rod at E-W Fence Line
		N15°W 28.33' 12" Maple
		N40°E 37.54' 10" Maple
		S25°E 22.57' 8" Maple
		S38°E 52.95' 20" Hemlock
		(Old scribed BT by others)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-2	December 11, 1995	Fd. 1/2" Rod & Cap #21559
Norman J. Quaine	P.S.#33984, Porter's Survey P.C.	by 3"X3" Wood Stake in E-W Fallen Fence Line
1996 P.I. Co. State Remonumentation		N15°W 28.32' 12" Maple (Beck's)
		N40°E 28.65' 10" Maple (Beck's)
		S38°E 54.43' 21" Hemlock (New Tag)
		S25°E 22.46' 9" Maple (New Tag)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-2  
 Left 1/2" Rod & Cap #21559 by 3"X3" Wood Stake in E-W Fallen Fence Line  
 N15°W 28.32' 12" Maple  
 N40°E 28.65' 10" Maple  
 S38°E 54.43' 21" Hamlock  
 S25°E 22.46' 9" Maple

Ratified by Peer Group in accordance with P.A. 345  
 Chairman *Delmer E. Porter*  
 Date 5/22/96

\*Witness tags & nails.

Porter's Survey P.C.

Signed by Norman J. Quaine  
 Surveyor's Michigan License No. 33984

Date May 29, 1996