

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle Located In: Corner Code #
(County)

1. Public Land Survey T34NR 5E C-3
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

PRESQUE ISLE COUNTY
RECORDED

96 JUN -4 AM 11:26

Janet M. Slamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Norman J. Quaine, in a field survey on Dec. 8, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3			•										
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-3	May 5, 1948	Sept. 29, 1978	Nov. 9, 1979
1856	Survey by Donald	LCRC, Delmer E.	LCRC, Delmer E. Porte
Sec Subdivision	A. Marlatt, R.S.	Porter, LS#15410	LS#15410
by Alfred Millerd	Scott & Assoc.	Fd 3/8" Rod at Int.	Fd 1/2" Rod - removed
Deputy Surveyor	Alpena, MI	N64° E 66.63' 12" Apple	& set conc mon with
Sec Post Cor Sec	Survey shows Sec.	N40° W 55.32' 14" Apple	brass cap
5,6,7 & 8	6 Subdivision	S59° W 103.00' P. Pole	N40° W 55.32' 14" Appl
Beech 10 N60E 33	Makes no physical		N64° E 66.63' 12" Apple
Sugar 11 S25W 14	reference to cor:		S59° W 103.00' P. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3	December 8, 1995	Oct. 31, 1980
Norman J. Quaine PS#33984	Porter's Survey P.C.	Survey recorded Liber 237, Page 876
P. I. County State Remonumentation	Fd. 1/2" Rod & Cap (illegible)	Delmer E. Porter LS#15410
N73° E 94.90' P. Pole	S61° W 98.82' P. Pole	4" Conc Mon with brass cap
		N64° E 66.63' 12" Apple
		S59° W 103.00' P. Pole
		N40° W 55.32' 14" Apple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3	Left 1/2" Rod & Cap (illegible)	Aug. 3, 1993, Survey by James A. Beck
In Road Int.	N43° W 59.48' 5" Twin Box Elder	P.S. #21559
N07° W 117.06' P. Pole	N73° E 94.90' P. Pole	Found 1/2" Iron Rod
S61° W 98.82' P. Pole		S15° E 88.71' Near face of stop sign pos
		S45° W 71.80' Near face of road sign pos
		N40° W 55' +/- Stump of tree
		N65° E 94.93' PK in S side power pole
		S55° W 98.84' in E'ly side power pole

*Witness tags & nails.

Porter's Survey P.C.

Signed by Norman J. Quaine Date MAY 29, 1996

Surveyor's Michigan License No. 33984

Ratified by Peer Group
in accordance with P.A. 345

Chairman Delmer E. Porter

Date 5/22/96