

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 318 PAGE 723

For corners in
Presque Isle
(County)

Located In:

Corner Code #

- | | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>34N</u> | R | <u>5E</u> | <u>D-1</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

PRESQUE ISLE COUNTY
 RECORDED

96 JUN 13 PM 12:23

Janet M. Lamb
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ronald Bischer, in a field survey on 3-20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-1
- 1840 John Hodgson Set Wood Post
- N62°W 12 links 12" Hemlock
- N18°E 13 links 7" Hemlock
- 4-14-78 Delmar Porter found P.K. Nail set by Scott in 1970. Set 1/2" Rod & Cap and Mon. box. left 3 witnesses
- 9-14-92 James Beck found 1/2" rod in Mon. box left 3 witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 3-20-96 Ronald Bischer found 1/2" Rod & Cap #15410 in Mon. box.
- North 34.28' Power pole
- N60°E 96.49' 6" Pine



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1
- 3-20-96 Ronald Bischer
- 1/2" Rod & Cap #15410 in Mon. Box
- North 34.28' Power pole
- N60°E 96.49' 18" White Pine
- S74°E 133.67' Power pole
- N27°E 39.18' 8" Fir

Ratified by Peer Group
 in accordance with P.A. 345

Chairman *Delmar Porter*
 Date 6/12/96

Signed by Ronald R. Bischer

Date 6-6-96

Surveyor's Michigan License No. 22428