

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)

Located In:

Corner Code #

- | | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>34N</u> | R | <u>5E</u> | <u>D-3</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

PRESQUE ISLE COUNTY
RECORDED

96 JUN 13 PM 12: 23

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald Bischer, in a field survey on 3-20, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-3
1856 Alfred Millend Set Wood Post
East 5 links 10" Cedar
West 14 links 12" Cedar
9-12-80 Delmar Porter found RxR Spike- Est. by D. MacNeill left 2 witnesses
9-23-80 Ronald Bischer found RxR Spike left 2 witnesses
2-4-91 James Beck 1/2" Iron left 4 witnesses. (witnesses are believed to be for E-3. Filing shows same wit. for both corners.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3
3-20-96 Ronald Bischer Found 1/2" Rod, set cap #22428
N05°E 77.75' 24" Ash
S28°W 68.48' 6" Ash



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3
Ronald Bischer 3-20-96
1/2" Rod & Cap #22428
N05°E 77.75' 26" Ash
S23°W 68.48' 8" Ash
S45°E 55.15' 6" Ash
S43°W 53.80' 7" Ash

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmar & Porter*
Date 6/12/96

Signed by Ronald R. Bischer

Date 6-6-96

Surveyor's Michigan License No. 22428