

1056

LAND CORNER RECORDATION CERTIFICATE LIBER 318 PAGE 725  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Presque Isle Located In: Corner Code #  
(County)

- 1. Public Land Survey T 34N R 5E D-5
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

PRESQUE ISLE COUNTY  
RECORDED

96 JUN 13 PM 12:23

*Janice M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Ronald Bischer, in a field survey on 3-28, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:

D-5  
 1856 Alfred Millend Set Wood Post  
 East 9 links 12" Sugar  
 West 14 links 12" Sugar  
 4-14-78 Delmar Porter found 1"x4" Iron - set Monument Box  
 left 3 witnesses  
 6-14-94 Ronald Bischer Refers to corner as "plow point" in Mon. box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5  
 3-28-96 Ronald Bischer Found Plow Point in Mon. Box  
 S55° E 62.07' 18" Maple  
 S05° E 31.04' 18" Maple  
 S48° W 42.84' 24" Maple

Ratified by Peer Group  
 in accordance with P.A. 345  
 Chairman *Delmar E. Porter*  
 Date 6/12/96



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5  
 3-28-96 Ronald Bischer  
 Plow Point in Mon. Box  
 S55° E 61.90' 18" Maple  
 S05° E 31.04' 22" Maple  
 S48° W 42.65' 37" Maple  
 N59° E 81.85' Power pole

Witness tag #31591-  
 T. Fabis- on all  
 four witnesses.

Signed by Ronald B. Bischer Date 6-6-96  
 Surveyor's Michigan License No. 22428