

1058

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 318 PAGE 727

For corners in

Presque Isle
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 34N R 5E D-9
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Section S T R

PRESQUE ISLE COUNTY
RECORDED

96 JUN 13 PM 12:24

Jane M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Ronald Bischer, in a field survey on 3-27, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-9
1856 Alfred Millend Set Wood Post
N70°W 7 links 8" Beech
S70°E 36 links 8" Beech

4-4-78 Delmar Porter found 1" Rod (Scott 1955), set 1/2" rod in Mon. box. left 3 witnesses
3-25-94 James Beck found 1/2" Rod & Cap #15410 in Mon Box left 5 witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9
3-27-96 Ronald Bischer Found 1/2" Rod & Cap #15410 in Mon. box
S66°E 86.54' 18" Maple stump
N70°E 42.80' Urd cable marker post
S50°W 50.25' Stop sign post
S70°W 80.50' 4" Apple
N46°W 40.30' P.pole



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9
3-27-96 Ronald Bischer
1/2" Rod & Cap #15410 in Mon. Box
S66°E 86.54' 18" Maple stump
N63°E 42.80' Cable post
S53°W 47.62' Stop sign
S67°W 80.50' 4" Apple
N42°W 40.30' Power pole

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmar Porter*
Date 6/12/96

Signed by Ronald R. Bischer

Date 6-6-96

Surveyor's Michigan License No. 22428