

1261

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34 N R 5 E E-1

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

PRESQUE ISLE COUNTY
RECORDED

96 JUL 12 AM 11:37

Janice M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James A. Beck, in a field survey on Jan 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1 Corner on Township line Common to Sections 4 AND 5

G.L.O. 1856 Beech 10 S28W 6
Alfred Merd Sugar 15 S82E 37

Jan 23, 1990
Recordation certificate
P.A. 1974 by J. Beck
Reg. no. 21559

Found 1/2" rod and cap in mon. box
N 44°30'E 49.00' 8" Cedar
S 49°W 49.49' Power Pole
N 10°E 54.59' 8" Cedar
N 10°W 34.5' guy pole

Sep. 25, 1972
Recordation certificate
P.A. 74 by R.E. Alonen
Reg. No. 12042

5/8" steel pin
8" Cedar N 44°30'E 49.67' (nail)
power pole S49°15'W 49.30' (nail)
tel. cable marker S32°30'E 44.90'

Sep. 25, 1978
Recordation certificate
P.A. 1974 by Delmer Porter
Reg. no. 15410

*E-1 3/4" bar (Scott 1970)
N 10°E 54.59' 8" Cedar
Due North 59.15' Fe. Post

May 12, 1995
P.A. 132 survey by
J. Beck P.S. no. 21559

N 44°30'E 49.00' 8" Cedar
S 49°W 49.49' Power Pole
N 10°E 54.49' 8" Cedar
N 10°W 34.5' guy pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1
1996 Remonumentation
by James A. Beck

found 1/2" iron rod with 15410 cap in monument box
and witnesses

N 44°30'E 49.10' 15410 tag in 10" Cedar
S 49°W 49.49' 15410 tag in power pole
N 10°E 54.59' 15410 tag in 10" Cedar
N 10°W 34.48' 21559 tag in guy pole

Ratified by Peer Group
in accordance with P.A. 345


Chairman *Delmer Porter*

Date 5/22/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1
1/2" iron rod with 15410 cap in monument box

Witnesses:
N 44°30'E 49.10' 15410 tag in 10" Cedar
S 49°W 49.49' 15410 tag in power pole
N 10°E 54.59' 15410 tag in 10" Cedar
N 10°W 34.48' 21559 tag in guy pole



Signed by James A. Beck
Surveyor's Michigan License No. 21559

Date June 17, 1996