

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T 34N R 5E	E-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

PRESQUE ISLE COUNTY  
RECORDED

96 JUL 12 AM 11:38

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James A. Beck, in a field survey of March 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-4  
G.L.O. 1856  
Alfred Millerd  
"Set or. Sec. post"  
Beech 12 N56°W 43  
Sugar 11 S72°E 33  
Sep. 25, 1978  
P.A. 74 Recordation  
by Delmer Porter  
Reg. No. 15410  
"Set 1/2" rod in Mon. Box  
halfway midway"  
Witnesses:  
N57°W 47.15' 6" Maple  
N 85°W 43.78' 4" Maple  
S63°W 47.61' 3" Maple


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4  
1996 Remonumentation by  
James A. Beck  
found monument box, could not remove cover  
witnesses are to center of cover  
witnesses:  
N 57°W 47.15' 21559 tag in 13" maple  
N 85°W 43.78' 7" Maple  
S 63°W 47.61' 8" Maple

Atified by Peer Group  
in accordance with P.A. 345,  
Chairman *Delmer Porter*  
Date 5/22/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4  
1996 Remonumentation by  
James A. Beck  
Center of cover of monument box  
witnesses:  
N 57°W 47.15' 21559 tag in 13" maple  
N 85°W 43.78' 7" Maple  
S 63°W 47.61' 8" Maple  
N 41°E 26.28' 21559 tag top of West face of guard post  
S 72°E 15.47' 21559 tag top of North face of guard post  
S 22°E 31.95' 21559 tag top of West face of guard post



Signed by *James A. Beck*  
Surveyor's Michigan License No. 21559

Date June 17, 1996

#9120