

1270

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 319 PAGE 117

For corners in

Table with columns: Located In: (Presque Isle County), Corner Code #, and survey details (1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec.)

PRESQUE ISLE COUNTY RECORDED

96 JUL 12 AM 11:39

Signature of Janet M. Lamb, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, James A. Beck, in a field survey on May 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a circled '3' at row 2, column G.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2 Oct. 17, 1978 June 24, 1988 Corner set and recorded subsequent to finding old recorded corner at cor 3 and 4 on Town Line (G1)
G.L.O. 1856 Alfred Millerd P.A. 1974 Recordation by Ronald Bischer Reg. No. 22428 James A. Beck Reg. no. 21559 1/2" rod and L.L.S. 21559 cap Witnesses: S 51W 13.78' 8" Balsam N21W 16.52' 9" Birch N 75W 30.80' 9" Poplar West .8' 1/2" rod
" Set gr. Sec. Post" Cedar 8 N70W 18 B. Ash 10 S55E 19 1/2" rod Witnesses: N 21W 16.44' 8" Birch N58E 17.09' 7" B. Ash S 51W 13.03' 6" Balsam R. Bischer set by Single proportion

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 1996 Remonumentation by James A. Beck P.S. 21559 found 1/2" iron rod and L.L.S. 21559 cap Witnesses: S 51W 13.78' 9" Balsam N21W 16.52' 9" Birch N 75W 30.80' 10" Poplar West 0.8' 1/2" rod and 15410 cap

Ratified by Peer Group in accordance with P.A. 346 Chairman [Signature] Date 5/22/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 1996 Remonumentation by James A. Beck P.S. 21559 1/2" rod and L.L.S. 21559 cap Witnesses: S 51W 13.78' 9" Balsam N21W 16.52' 9" Birch N 75W 30.80' 10" Poplar West 0.8' 1/2" rod and 15410 cap South 43.74' 14" Maple P.S. 21559 tags set in all witness trees



Signed by [Signature] Surveyor's Michigan License No. 21559

Date June 17, 1996