

1275

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 319 PAGE 122

PRESQUE ISLE COUNTY
RECORDED

96 JUL 12 AM 11:40

Janet M. Sand
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Presque Isle
(County)

Located In: Corner Code #

1. Public Land Survey T 34N R 5E G-7
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James A. Beck, in a field survey on Feb 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7 G.L.O. 1856 Alfred Millerd
" Set post Cor. of Secs. 15, 16, 21, & 22 "
Hemlock 12 N73E 18
Y. Birch 14, S58W 13

Sep. 25, 1978
P.A. 74 Recordation
by Delmer Porter
Reg. No. 15410
1/2" rod & cap in Mon. Box
N29°W 56.47' Fe. Cor.
S51°W 58.89' buried cable sign
S25°E 66.70' P. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 found 1/2" iron and 15410 cap
in monument box at centerline road intersection
N 29°W 56' + or- fence corner post leaning

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer Porter*
Date 5/22/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 1/2" iron and 15410 cap
in monument box at centerline road intersection

N 29°W 56' + or- fence corner post leaning
S 25°E 64.92' P.S. 21559 tag in power pole (appears new)
S 40°E 41.12' center of road sign post at road level
S 58°W 66.36' Northeast corner of top of underground cable marker post
N 50°W 60.69' Southeast corner of top of underground cable marker post



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date June 17, 1996