

1285

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 319 PAGE 133

For corners in

Presque Isle
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34N R 5E G-9
T R
T R
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

PRESQUE ISLE COUNTY
RECORDED

96 JUL 12 AM 11:41

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, James A. Beck, in a field survey on Mar 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A circled 'X' is located at row 9, column G.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Dec. 9, 1976
P.A. 132 Survey Survey Recorded
by Delmer Porter in Liber 215, Page 882
G.L.O. 1856 Reg. No. 15410
Alfred Millerd " NW Sec cor, iron raised with PK "
" Set post Cor. Secs. 21, 22, 27, & 28"
Cedar 8 N30E 26 Witnesses:
Cedar 8 S70W 9 N38W 46.47' 6" Cedar
West 29.88' FE COR
East 34.41 FE COR

Ratified by Peer Group
in accordance with P.A. 345
Chairman [Signature]
Date 5/22/96

PART "A" CONTINUED ON REVERSE SIDE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 1996 Remonumentation found 1/2" iron in monument box, set P.S. 21559 cap
by James A. Beck
Witnesses:
N 38W 46.47' 15410 tag in 8" Cedar
West 30.16' 15410 tag in fence post
S 86E 34.41' 15410 tag in fence cor post



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 1996 Remonumentation found 1/2" iron in monument box, set P.S. 21559 cap
by James A. Beck on iron
corner falls in centerline of North-South
tar surface road at fences Easterly and Westerly extended
Witnesses:
N 38W 46.47' 15410 tag in 8" Cedar
West 30.16' 15410 tag in fence post
S 86E 34.41' 15410 tag in fence cor post
S 15E 118.54' 21559 tag in power pole
EAST 33.00' 1/2" iron and 15410 cap

Signed by [Signature]
Surveyor's Michigan License No. 21559

Date June 17, 1996

PART "A" CONTINUED CORNER G-9

Dec. 20, 1976  
P.A. 74 Recordation  
by Ronald Bischer  
Reg. No. 22428

P.K. Nail  
West 29.88' Fe. Cor.  
S 86°E 34.41' Fe. Cor.  
N38°W 46.47' 6" Cedar

Sep. 25, 1978  
P.A. 74 Recordation  
by Delmer Porter  
Reg. No. 15410

1/2" rod & cap in Monument Box  
N38°W 46.47' 6" Cedar  
Due West 29.88' Fe. Cor.  
S 86°E 34.41' Fe. Cor.

Jan 4, 1980  
P.A. 132 Survey  
by Delmer Porter  
Reg. No. 15410

" Iron raised with P.K. "  
N38°W 46.47' 6" Cedar  
Due West 29.88' Fe. Cor.  
S 86°E 34.41' Fe. Cor.

Survey recorded  
Liber 234, Page 450

May 22, 1986  
P.A. 132 Certificate  
by James A. Beck  
Reg. No. 21559

1/2" rod and cap in monument box  
N 38°W 46.47' 6" Cedar  
West 29.88' Fence Cor.  
S 86°E 34.41' Fence Cor.

*James A. Beck*

