

1271

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 319 PAGE 124

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T 34N R 5E	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED

96 JUL 12 AM 11:40

June M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Mar 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-11 G.L.O. 1856 Alfred Millerd " Set post Corner of Secs 27, 28, 33 & 34" Sugar 14 N22W 48 Beech 14 S60E 31	Dec. 12, 1976 P.A. 74 Recordation by Ronald Bischer Reg. No. 22428 "found 1/2" rod" Witnesses: N46°E 46.45' Power pole S 21°E 68.44' Tele. Cable Box	Sep. 25, 1978 P.A. 74 Recordation by Delmer Porter Reg. No. 15410 1/2" rod in Mon. Box Witnesses: N 46°W 49.89' Fe. Cor. N46°E 46.45' Power pole S 21°E 68.44' Tel. Cable Box	Oct. 4, 1994 P.A.74 Recordation by James A. Beck Reg. No. 21559 found P.K. nail over mon box Witnesses: N 46°E 46.45', R.L.S. 15410 tag in P. Pole N 78°E 73.74' stop sign post S 28°W 82.40' P.S. 21559 tag in 3" Ash S 81°W 95.31' stop sign
--	---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 1996 Remonumentation
by James A. Beck
found 1/2" iron 8" deep in monument box, set 21559 cap on iron
witnesses:
N 46°E 46.45' 15410 tag in power pole
N 78°E 73.74' stop sign post
S 28°W 82.40' 21559 tag in 3" Ash
S 81°W 95.31' stop sign post

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmer Porter*
Date 5/22/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 1996 Remonumentation
by James A. Beck
1/2" iron rod with P.S 21559 cap, 8" deep in monument box
corner falls at centerline intersection of tar surface road North
and South, gravel road to West and East
witnesses:
N 46°E 46.45' 15410 tag in power pole
N 78°E 73.74' stop sign post
S 28°W 82.40' 21559 tag in 3" Ash
S 81°W 95.31' stop sign post



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date June 17, 1996