

1996 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 319 PAGE 125

For corners in

Presque Isle

(County)

Located In:

Corner Code #

1. Public Land Survey

T 34N R 5E G-12
 T R
 T R
 T R
 S T R
 S T R
 S T R
 S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

PRESQUE ISLE COUNTY
RECORDED

96 JUL 12 AM 11:40

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, James A. Beck, in a field survey on Apr 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12
 G.L.O. 1856 Oct. 4, 1994 Witnesses:
 Alfred Millerd P.A. 74 Recordation S87°E 62.13' 16" Cedar
 " Set cr. Section post" by James A. Beck S 80°E 60.95' 16" Apple
 Hemlock 7 S10W 9 Reg. No. 21559 S 50°W 159.23' 6" Ash
 Sugar 12 N70E 9 Set 1/2" iron and P.S. 21559 S 64°W 134.8' 11" Basswood
 cap by single proportion

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12
 NOTE:
 Corner from October 1994 set in error midway on line between Section Corners; reset corner at proportionate measure to G.L.O. as G.L.O. resurvey caused Sections 33 and 34 to be fractional
 Corner from 1994 recordation is removed, search of record and field did not reveal any other usage of corner

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *[Signature]*
 Date 5/22/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 1996 Remonumentation
 by James A. Beck
 P.S. 21559
 set 1/2" iron rod and 21559 cap
 in monument box
 S 82°E 62.03' 16" Cedar
 S 74°E 61.41' 16" Apple
 S 49°W 161.95' 6" Ash
 S 65°W 136.68' 11" Basswood
 (P.S. 21559 tags in all trees")



Signed by *James A. Beck* Date June 17, 1996
 Surveyor's Michigan License No. 21559